BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of the Work: Improvements to roads and drains SC colony at Maruthinagara and BB nagara in ward no. 8, kodigehalli, kodigehalli sub division

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
1	114.36	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	cum	83.16	9510.18	Rupees Eighty Three and Sixteen Paise Only
2	43.65	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unservicea ble material and stacking the serviceable material with all lifts complete as per specifications.- Rubble stone masonry in cement mortar	cum	250.56	10936.94	Rupees Two Hundred Fifty and Fifty Six Paise Only
3	59.67	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5070.60	302562.70	Rupees Five Thousand Seventy and Sixty Paise Only
4	39.78	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5991.84	238355.40	Rupees Five Thousand Nine Hundred Ninety One and Eighty Four Paise Only
5	397.80	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift	sqm	97.20	38666.16	Rupees Ninety Seven and Twenty Paise Only
6	26.00	Providing groove cutting for cement pavement wifth of 5mm to 10mm and depth 800mm-100mm including cost of cutting machine, generator and HOM of machinery, including cost of blade, coolant etc, including cleaning of groove and providing sand and hot bitumen fillarsm and filler metal etc including of conveyance of all materials, labour, lead and lift charge	Rm	124.20	3229.20	Rupees One Hundred Twenty Four and Twenty Paise Only
7	384.60	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. (Approved data rate enclosed)	sqm	1600.00	615360.00	Rupees One Thousand Six Hundred Only
8	240.00	Removing B.S Slab of Drain and stacking with all leads and lifts etc., complete as directed	sqm	63.72	15292.80	Rupees Sixty Three and Seventy Two Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

A.E. (W.O.) 5/8/15

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
9	40.00	Refixing stone slabs of drains and pointing in C.M (1:3) with all leads and lifts etc., complete as directed	sqm	78.84	18921.60	Rupees Seventy Eight and Eighty Four Paise Only
10	158.01	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	78.97	12478.05	Rupees Seventy Eight and Ninety Seven Paise Only
		Total			1265313.03	

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/8/16

05/08